

National Institute of Technology Calicut

NIT Campus P.O, Calicut, Kerala – 673 601, India

Engg/D1/265/2022-23

15.03.2023

Quotation Notice

Sealed, item rate quotations are invited for direct execution (No sub-contracting) for the below work from eligible candidates.

Sl. No.	Name of work with PAC and EMD	Cost of Quotation Form
1.	Providing sand bag bund over existing check dam of pump house river 2022-23 . PAC – Rs.1,43,876/- EMD – Rs. 2,900/-	Rs.500/- +Tax Rs.90/-

1. Quotation forms can be had from the office of the Superintending Engineer, only up to **01.00 PM** on all working days from **15.03.2023 to 23.03.2023**.
2. Last date and time of receiving quotation will be **23.03.2023, 3.30pm** and it will be open at 04.00 pm on the same day. If the day becomes to be a holiday, the same will be extended to next working day of the institution.
3. The construction of bund to be completed within 7 days after getting the work order from Engineering Unit
4. The needful sand for filling bags can be taken from the river bed and it is not permitted to shifting any quantity of sand from the site except for bund work.
5. Sand bags for the bund to be laid with proper bond and ensure that it will not be collapse due to any normal forces.
6. The repairs/refixing work should be done without any delay and the rate will be same as approved rates for constructions of each bag.
7. The payment will be made after satisfactory completion of the work.
8. The rate should be quoted in sealed cover for each bag without any over writing in words and figures, including all taxes.
9. Conditional quotations will not be acceptable. The conditions laid down by the Institute are final and binding on all Contractors.

The Director of the Institute reserves the right to accept or reject any quotations without assigning any reasons


Superintending Engineer (i/c)
Engineering Unit, NIT Calicut

Schedule A:

SI No	Description	Qty	Unit	Rate	Amount
1.1	Filling sand in 3/4 portion of plastic cement bags and laying bags over the existing bund one by one properly till the storage of river water raised not less than 45cm from the top level of existing check dam.The charges including all labour charges for filling sand in bags, cost of empty plastic bags, all conveyance charges and all laying charges.The work should be done as per the instruction of the department Engineer.				
1.1.1	Providing sand bag bund above check dam across Cherupuzha river near pump house of NITC,towards the storage of raw water for increasing the level of water in the reservoir.	900	Nos		
1.1.2	Laying sand bag bund at the damaged portion of bund failed due to heavy flow of water or due to any other natural effects.The charges for replacing sand bags are same as approved charges for the construction of bund.	190	Nos		
Total					

I,..... agree to execute the work by accepting the conditions at an amount of

.....

.....(Here enter the quoted amount in words) .


Superintending Engineer (i/c)
Engineering Unit, NIT Calicut
